



11815 NE 99th Street, Suite 1294  
Vancouver, WA 98662  
Voice: 360-574-3058  
Fax: 360-576-0925  
Web: <https://www.swcleanair.gov>  
Email: [Tina@swcleanair.gov](mailto:Tina@swcleanair.gov)

## Notice of Intent to Remove Asbestos

Case #: 24-196

Amendment: 0

Date Received: 3/28/2024

Date Paid: 3/28/2024

SWCAA Fee: \$369.00

Receipt #: 153493005

**This notification MUST be present at all times at the asbestos project sit**

Quantity to be removed: 768 Square Feet 0 Linear Feet

Workshift days: M T W Th F

Project starting date: 4/8/2024 Project Completion date: 4/19/2024

Workshift hours: 8:00 am - 4:30pm

Site Name: TMG ACM & Demo\_5901

Site address: 5901 NE 6th Ave

Location of Asbestos: Ceiling

City/State/Zip: Vancouver

WA 98665

☐ Demolition of Structure (Notification of Demolition required)

County: CLARK COUNTY

☒ Asbestos survey conducted?

No survey reason:

AHERA Inspector: Emily Weiss

Certification #: BI/NES-07-26-23-02

### Material to be Removed:

- |                                       |   |                              |                                      |  |                                    |
|---------------------------------------|---|------------------------------|--------------------------------------|--|------------------------------------|
| <input type="checkbox"/> Fireproofing | <input checked="" type="checkbox"/> Popcorn Ceiling | <input type="checkbox"/> CAB | <input type="checkbox"/> Sheet Vinyl | <input type="checkbox"/> Boiler Insulation | <input type="checkbox"/> Duct Tape |
| <input type="checkbox"/> Duct Paper   | <input type="checkbox"/> Mag Pipe Insulation        |                              | <input type="checkbox"/> Air Cell    | <input type="checkbox"/> CA Pipe           | <input type="checkbox"/> VAT       |
| <input type="checkbox"/> Other        |   |                              |                                      |  |                                    |

### Control Methods:

- |   |                                    |   |                                       |   |  |
|---|------------------------------------|---|---------------------------------------|---|--|
| <input checked="" type="checkbox"/> N.P Enclosure                                 | <input type="checkbox"/> Glove Bag | <input type="checkbox"/> Mini Enclosure | <input type="checkbox"/> Wrap and Cut | <input checked="" type="checkbox"/> Water | <input checked="" type="checkbox"/> HEPA Vac |
| <input checked="" type="checkbox"/> Other Manual Methods, PAPR, Critical Barriers |                                    |   |                                       |   |  |

Asbestos Contractor: 3 Kings Environmental Inc.

Phone: 253-750-4143

Mailing Address: PO Box 280, Battle Ground, WA, 98604

Email: [jhawks@3kingsinc.com](mailto:jhawks@3kingsinc.com)

Certification ##: ABCN00001318

Supervisor: Emily Weiss

Phone: 253-750-4143

Property Owner: The Management Group, Inc.

Phone: 360-892-4000

Mailing Address: 7710 NE Vancouver Mall Dr., Ste B, Vancouver WA 98662

Asbestos Disposal Site: Wasco County Landfill: 2550 Steele Rd, The Dalles, OR, 97058-

**I DO HEREBY CERTIFY THAT THE INFORMATION CONTAINED IN THIS NOTIFICATION IS,  
TO THE BEST OF MY KNOWLEDGE, ACCURATE AND COMPLETE.**

Submitter Name: Kristine Bantz

Representing: 3 Kings Environmental

Submitter Title: Office Admin

Date Submitted: 3/28/2024

Reviewed by SWCAA: Mihai Voivod

☒ Approved



11815 NE 99th Street, Suite 1294  
Vancouver, WA 98662  
Voice: 360-574-3058  
Fax: 360-576-0925  
Web: <https://www.swcleanair.gov>  
Email: [Tina@swcleanair.gov](mailto:Tina@swcleanair.gov)

## Notice of Intent to Remove Asbestos

Case #: 24-196

Amendment: 0

Date Received: 3/28/2024

Date Paid: 3/28/2024

SWCAA Fee: \$369.00

Receipt #: 153493005

**This notification MUST be present at all times at the asbestos project sit**



**The Identification Specialists**

Analysis Report  
prepared for  
3 Kings Environmental Inc.

**Report Date: 3/15/2024**

**Project Name: TMG ACM & Demo**

**Project #: 224032-5901**

**SanAir ID#: 24015117**



NVLAP LAB CODE 200870-0

10501 Trade Court | North Chesterfield, Virginia 23236  
888.895.1177 | 804.897.1177 | fax: 804.897.0070 | [IAQ@SanAir.com](mailto:IAQ@SanAir.com) | [SanAir.com](http://SanAir.com)



SanAir ID Number

24015117

FINAL REPORT

3/15/2024 9:13:35 AM

**Name:** 3 Kings Environmental Inc.  
**Address:** PO Box 280  
Battle Ground, WA 98604  
**Phone:** 360-666-5464

**Project Number:** 224032-5901  
**P.O. Number:** 12024-071  
**Project Name:** TMG ACM & Demo  
**Collected Date:** 3/11/2024  
**Received Date:** 3/14/2024 10:35:00 AM

Dear Emily Weiss,

We at SanAir would like to thank you for the work you recently submitted. The 31 sample(s) were received on Thursday, March 14, 2024 via UPS. The final report(s) is enclosed for the following sample(s): 01, 02, 03, 04, 05, 06, 07, 08, 09, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31.

These results only pertain to this job and should not be used in the interpretation of any other job. This report is only complete in its entirety. Refer to the listing below of the pages included in a complete final report.

Sincerely,

A handwritten signature in black ink that reads "Sandra Sobrino".

Sandra Sobrino  
Asbestos & Materials Laboratory Manager  
SanAir Technologies Laboratory

Final Report Includes:

- Cover Letter
- Analysis Pages
- Disclaimers and Additional Information

Sample conditions:

- 31 samples in Good condition.



SanAir ID Number

24015117

FINAL REPORT

3/15/2024 9:13:35 AM

**Name:** 3 Kings Environmental Inc.  
**Address:** PO Box 280  
Battle Ground, WA 98604  
**Phone:** 360-666-5464

**Project Number:** 224032-5901  
**P.O. Number:** 12024-071  
**Project Name:** TMG ACM & Demo  
**Collected Date:** 3/11/2024  
**Received Date:** 3/14/2024 10:35:00 AM

Analyst: Moore, Brandi

## Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic	Components		Asbestos Fibers
	Appearance	% Fibrous	% Non-fibrous	
01 / 24015117-001 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Sheet Flooring	Beige Non-Fibrous Heterogeneous	15% Cellulose	85% Other	None Detected
01 / 24015117-001 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Mastic	Cream Non-Fibrous Homogeneous		100% Other	None Detected
01 / 24015117-001 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Sheet Flooring	Tan Non-Fibrous Heterogeneous	15% Cellulose	85% Other	None Detected
01 / 24015117-001 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Mastic	Cream Non-Fibrous Homogeneous		100% Other	None Detected
01 / 24015117-001 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Sheet Flooring	Yellow Non-Fibrous Heterogeneous	20% Cellulose 5% Synthetic	75% Other	None Detected
01 / 24015117-001 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Mastic	Brown Non-Fibrous Homogeneous		100% Other	None Detected
02 / 24015117-002 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Sheet Flooring	Beige Non-Fibrous Heterogeneous	15% Cellulose	85% Other	None Detected
02 / 24015117-002 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Mastic	Cream Non-Fibrous Homogeneous		100% Other	None Detected
02 / 24015117-002 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Sheet Flooring	Tan Non-Fibrous Heterogeneous	15% Cellulose	85% Other	None Detected
02 / 24015117-002 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Mastic	Cream Non-Fibrous Homogeneous		100% Other	None Detected

Analyst: *Brandi Moore*

Approved Signatory: *Ronald A. D. H.*

Analysis Date: 3/15/2024

Date: 3/15/2024



SanAir ID Number

24015117

FINAL REPORT

3/15/2024 9:13:35 AM

**Name:** 3 Kings Environmental Inc.  
**Address:** PO Box 280  
Battle Ground, WA 98604  
**Phone:** 360-666-5464

**Project Number:** 224032-5901  
**P.O. Number:** 12024-071  
**Project Name:** TMG ACM & Demo  
**Collected Date:** 3/11/2024  
**Received Date:** 3/14/2024 10:35:00 AM

Analyst: Moore, Brandi

**Asbestos Bulk PLM EPA 600/R-93/116**

SanAir ID / Description	Stereoscopic	Components		Asbestos Fibers
	Appearance	% Fibrous	% Non-fibrous	
02 / 24015117-002 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Sheet Flooring	Tan Non-Fibrous Heterogeneous	15% Cellulose	85% Other	None Detected
02 / 24015117-002 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Mastic	Cream Non-Fibrous Homogeneous		100% Other	None Detected
02 / 24015117-002 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Sheet Flooring	Yellow Non-Fibrous Heterogeneous	20% Cellulose 5% Synthetic	75% Other	None Detected
02 / 24015117-002 3 Layer SVF & Mastic/Laundry, Kitchen, Dining, Mastic	Brown Non-Fibrous Homogeneous		100% Other	None Detected
03 / 24015117-003 Sheet Vinyl Floor/Bathroom, Sheet Flooring	Beige Non-Fibrous Heterogeneous	15% Cellulose	85% Other	None Detected
03 / 24015117-003 Sheet Vinyl Floor/Bathroom, Mastic	Yellow Non-Fibrous Homogeneous		100% Other	None Detected
04 / 24015117-004 Sheet Vinyl Floor/Bathroom, Sheet Flooring	Beige Non-Fibrous Heterogeneous	15% Cellulose	85% Other	None Detected
04 / 24015117-004 Sheet Vinyl Floor/Bathroom, Mastic	Yellow Non-Fibrous Homogeneous		100% Other	None Detected
05 / 24015117-005 Cove & Mastic/Kitchen, Cove Base	Brown Non-Fibrous Homogeneous		100% Other	None Detected
05 / 24015117-005 Cove & Mastic/Kitchen, Mastic	Various Non-Fibrous Homogeneous		100% Other	None Detected

Analyst: *Brandi Moore*Approved Signatory: *Ronald A. Dik*

Analysis Date: 3/15/2024

Date: 3/15/2024



SanAir ID Number

24015117

FINAL REPORT

3/15/2024 9:13:35 AM

**Name:** 3 Kings Environmental Inc.  
**Address:** PO Box 280  
Battle Ground, WA 98604  
**Phone:** 360-666-5464

**Project Number:** 224032-5901  
**P.O. Number:** 12024-071  
**Project Name:** TMG ACM & Demo  
**Collected Date:** 3/11/2024  
**Received Date:** 3/14/2024 10:35:00 AM

Analyst: Moore, Brandi

## Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic	Components		Asbestos Fibers
	Appearance	% Fibrous	% Non-fibrous	
06 / 24015117-006 Cove & Mastic/Laundry, Cove Base	Brown Non-Fibrous Homogeneous		100% Other	None Detected
06 / 24015117-006 Cove & Mastic/Laundry, Mastic	Various Non-Fibrous Homogeneous		100% Other	None Detected
07 / 24015117-007 Sink / Kitchen	White Non-Fibrous Homogeneous	5% Cellulose	95% Other	None Detected
08 / 24015117-008 Sink / Kitchen	White Non-Fibrous Homogeneous	5% Cellulose	95% Other	None Detected
09 / 24015117-009 GWB, Joint Compound, Texture/Bedrm 1 Walls, Wallboard	White Non-Fibrous Homogeneous	5% Cellulose	95% Other	None Detected
09 / 24015117-009 GWB, Joint Compound, Texture/Bedrm 1 Walls, Joint Compound	Tan Non-Fibrous Homogeneous		100% Other	< 1% Chrysotile
09 / 24015117-009 GWB, Joint Compound, Texture/Bedrm 1 Walls, Texture	Various Non-Fibrous Heterogeneous		100% Other	< 1% Chrysotile
10 / 24015117-010 GWB, Joint Compound, Texture/Bedrm 2 Walls, Wallboard	White Non-Fibrous Homogeneous	5% Cellulose	95% Other	None Detected
10 / 24015117-010 GWB, Joint Compound, Texture/Bedrm 2 Walls, Joint Compound	White Non-Fibrous Homogeneous		100% Other	< 1% Chrysotile
10 / 24015117-010 GWB, Joint Compound, Texture/Bedrm 2 Walls, Texture	White Non-Fibrous Homogeneous		100% Other	< 1% Chrysotile

Analyst: *Brandi Moore*

Approved Signatory:

*Brandi A. Moore*

Analysis Date: 3/15/2024

Date: 3/15/2024



SanAir ID Number

24015117

FINAL REPORT

3/15/2024 9:13:35 AM

**Name:** 3 Kings Environmental Inc.  
**Address:** PO Box 280  
Battle Ground, WA 98604  
**Phone:** 360-666-5464

**Project Number:** 224032-5901  
**P.O. Number:** 12024-071  
**Project Name:** TMG ACM & Demo  
**Collected Date:** 3/11/2024  
**Received Date:** 3/14/2024 10:35:00 AM

Analyst: Moore, Brandi

## Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic	Components		Asbestos Fibers
	Appearance	% Fibrous	% Non-fibrous	
11 / 24015117-011 GWB, Joint Compound, Texture/Living Rm Walls, Wallboard	White Non-Fibrous Homogeneous	5% Cellulose	95% Other	None Detected
11 / 24015117-011 GWB, Joint Compound, Texture/Living Rm Walls, Joint Compound	Tan Non-Fibrous Homogeneous		100% Other	< 1% Chrysotile
11 / 24015117-011 GWB, Joint Compound, Texture/Living Rm Walls, Texture	White Non-Fibrous Homogeneous		100% Other	< 1% Chrysotile
12 / 24015117-012 GWB, Joint Compound, Texture / Kitchen Walls, Wallboard	White Non-Fibrous Homogeneous	5% Cellulose	95% Other	None Detected
12 / 24015117-012 GWB, Joint Compound, Texture / Kitchen Walls, Joint Compound	White Non-Fibrous Homogeneous		100% Other	< 1% Chrysotile
12 / 24015117-012 GWB, Joint Compound, Texture / Kitchen Walls, Texture	Various Non-Fibrous Heterogeneous		100% Other	< 1% Chrysotile
13 / 24015117-013 Drywall, Joint Compound, Texture/Ceiling Laundry, Wallboard	White Non-Fibrous Homogeneous	5% Cellulose	95% Other	None Detected
13 / 24015117-013 Drywall, Joint Compound, Texture/Ceiling Laundry, Joint Compound	White Non-Fibrous Homogeneous		100% Other	< 1% Chrysotile
13 / 24015117-013 Drywall, Joint Compound, Texture/Ceiling Laundry, Texture	Various Non-Fibrous Heterogeneous		100% Other	< 1% Chrysotile

Analyst: *Brandi Moore*

Approved Signatory: *Rebecca A. D. H.*

Analysis Date: 3/15/2024

Date: 3/15/2024





SanAir ID Number  
**24015117**  
FINAL REPORT  
3/15/2024 9:13:35 AM

**Name:** 3 Kings Environmental Inc.  
**Address:** PO Box 280  
Battle Ground, WA 98604  
**Phone:** 360-666-5464

**Project Number:** 224032-5901  
**P.O. Number:** 12024-071  
**Project Name:** TMG ACM & Demo  
**Collected Date:** 3/11/2024  
**Received Date:** 3/14/2024 10:35:00 AM

Analyst: Moore, Brandi

**Asbestos Bulk PLM EPA 600/R-93/116**

SanAir ID / Description	Stereoscopic	Components		Asbestos Fibers
	Appearance	% Fibrous	% Non-fibrous	
14 / 24015117-014 Popcorn Ceiling/Kitchen	White Non-Fibrous Homogeneous		98% Other	2% Chrysotile
15 / 24015117-015 Popcorn Ceiling/Living Room				Not Analyzed
16 / 24015117-016 Popcorn Ceiling/Hall				Not Analyzed
17 / 24015117-017 Popcorn Ceiling/Bedrm 2				Not Analyzed
18 / 24015117-018 Popcorn Ceiling/Bedrm 1				Not Analyzed
19 / 24015117-019 Front Door Frame Caulk	Various Non-Fibrous Heterogeneous		100% Other	None Detected
20 / 24015117-020 Front Door Frame Caulk	Various Non-Fibrous Heterogeneous		100% Other	None Detected
21 / 24015117-021 Entry SVF	Tan Non-Fibrous Homogeneous		100% Other	None Detected
22 / 24015117-022 3 Tab Roof	Black Non-Fibrous Heterogeneous	5% Glass	95% Other	None Detected
23 / 24015117-023 3 Tab Roof	Black Non-Fibrous Heterogeneous	5% Glass	95% Other	None Detected

Analyst: *Brandi Moore*  
Analysis Date: 3/15/2024

Approved Signatory: *Ronald A. Dik*  
Date: 3/15/2024



SanAir ID Number

24015117

FINAL REPORT

3/15/2024 9:13:35 AM

**Name:** 3 Kings Environmental Inc.  
**Address:** PO Box 280  
Battle Ground, WA 98604  
**Phone:** 360-666-5464

**Project Number:** 224032-5901  
**P.O. Number:** 12024-071  
**Project Name:** TMG ACM & Demo  
**Collected Date:** 3/11/2024  
**Received Date:** 3/14/2024 10:35:00 AM

Analyst: Moore, Brandi

## Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic	Components		Asbestos Fibers
	Appearance	% Fibrous	% Non-fibrous	
24 / 24015117-024 Roof Paper	Black Fibrous Homogeneous	70% Cellulose	30% Other	None Detected
25 / 24015117-025 Roof Paper	Black Fibrous Homogeneous	70% Cellulose	30% Other	None Detected
26 / 24015117-026 Shower Surround & Mastic, Tile	White Non-Fibrous Heterogeneous	30% Cellulose	70% Other	None Detected
26 / 24015117-026 Shower Surround & Mastic, Mastic	Black Non-Fibrous Homogeneous		100% Other	None Detected
27 / 24015117-027 Shower Surround & Mastic, Tile	White Non-Fibrous Heterogeneous	30% Cellulose	70% Other	None Detected
27 / 24015117-027 Shower Surround & Mastic, Mastic	Black Non-Fibrous Homogeneous		100% Other	None Detected
28 / 24015117-028 Paper Under Hardwood Floor	Brown Fibrous Heterogeneous	50% Cellulose	50% Other	None Detected
29 / 24015117-029 Paper Under Hardwood Floor	Brown Fibrous Heterogeneous	50% Cellulose	50% Other	None Detected
30 / 24015117-030 Felt Paper Behind Siding	Black Fibrous Heterogeneous	65% Cellulose	35% Other	None Detected
31 / 24015117-031 Felt Paper Behind Siding	Black Fibrous Heterogeneous	65% Cellulose	35% Other	None Detected

Analyst: *Brandi Moore*

Approved Signatory:

*Ronald A. Dik*

Analysis Date: 3/15/2024

Date: 3/15/2024

## **Disclaimer**

This report is the sole property of the client named on the SanAir Technologies Laboratory chain-of-custody (COC). Results in the report are confidential information intended only for the use by the customer listed on the COC. Neither results nor reports will be discussed with or released to any third party without our client's written permission. The final report shall not be reproduced except in full without written approval of the laboratory to assure that parts of the report are not taken out of context. This report and any information contained within shall not be edited, altered, or modified in any way by any persons or agencies receiving, viewing, distributing, or otherwise possessing a copy of this final report. The laboratory reserves the right to perform amendments to any finalized report, of which shall supersede and make obsolete any previous editions. Such changes, modifications, additions, or deletions shall be effective immediately upon notice thereof, which may be given by means including but not limited to posting on the SanAir client portal website, electronic or conventional mail, or by any other means. The information provided in this report applies only to the samples submitted and is relevant only for the date, time, and location of sampling. The accuracy of the results is dependent upon the client's sampling procedure and information provided to the laboratory by the client on the COC. SanAir assumes no responsibility for the sampling procedure and will provide evaluation reports based solely on the sample(s) in the condition in which they arrived at the laboratory and information provided by the client on the COC, such as: project number, project name, collection dates, po number, special instructions, samples collected by, sample numbers, sample identifications, sample type, selected analysis type, flow rate, total volume or area, and start stop times that may affect the validity of the results in this report. Samples were received in good condition unless otherwise noted on the report. SanAir assumes no responsibility or liability for the manner in which the results are used or interpreted. This report does not constitute nor shall not be used by the client to claim product, process, system, or person certification, approval, or endorsement by NVLAP, NIST, NELAC, AIHA LAP, LLC or any other U.S. governmental agencies and may not be accredited by every local, state, and federal regulatory agencies. Samples are held for a period of 60 days. Fibers smaller than 5 microns cannot be seen with this method due to scope limitations. For NY state samples, method EPA 600/M4-82-020 is performed.

### NYELAP Disclaimer:

Polarized- light microscopy is not consistently reliable in detecting asbestos in floor covering and similar non-friable organically bound materials. Quantitative transmission electron microscopy is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos containing.

### Asbestos Accreditations

National Voluntary Laboratory Accreditation Program (NVLAP) Lab Code 200870-0  
City of Philadelphia Department of Public Health Air Management Services, Certification#ALL-460  
Commonwealth of Pennsylvania Department of Environmental Protection Number 68-05397  
California State Environmental Laboratory Accreditation Program Certificate Number 2915  
Colorado Department of Public Health and Environment Registration Number AL-23143  
Connecticut Department of Public Health Environmental Laboratory Registration Number PH-0105  
Massachusetts Department of Labor Standards Asbestos Analytical Services License Number: AA000222  
State of Maine Department of Environmental Protection License Number: LB-0075, LA-0084  
New York State Department of Health Laboratory ID: 11983  
State of Rhode Island Department of Health Certification No.: PCM00126, PLM00126, TEM00126  
Texas Department of State Health Services License Number: 300440  
Commonwealth of Virginia Department of Professional and Occupational Regulation Number: 3333000323  
State of Washington Department of Ecology Laboratory ID: C989  
State of West Virginia Bureau for Public Health Analytical Laboratory Number: LT000616  
Vermont Department of Health License Number: Asb-Co-An-000006  
Louisiana Department of Environmental Quality AI Number 212253, Certificate #05088



10501 Trade Ct., Suite 100  
N. Chesterfield, VA 23236  
804.897.1177 / 888.895.1177  
Fax 804.897.0070  
[sanair.com](http://sanair.com)

**Asbestos**  
**Chain of Custody**  
Form 140, Rev 7, 10/20/2022

SanAir ID Number

24015117

Company: <b>3 Kings Environmental, Inc.</b>	Project #: <b>224032-5901</b>	Collected by: <b>E. Weiss</b>
Address: <b>Po Box 280</b>	Project Name: <b>TMG ACM &amp; Demo</b>	Phone #: <b>253-750-4143</b>
City, St., Zip: <b>Battle Ground, WA 98604</b>	Date Collected: <b>3/11/2024</b>	Fax #: <b>360-666-8202</b>
State of Collection: <b>WA</b> Account#: <b>2344</b>	P.O. Number: <b>12024-071</b>	Email: <b>eweiss@3kingsinc.com</b>

Bulk			Air			Soil		
ABB	PLM EPA 600/R-93/116	<input checked="" type="checkbox"/>	ABA	PCM NIOSH 7400	<input type="checkbox"/>	ABSE	PLM EPA 600/R-93/116 (Qual.)	<input type="checkbox"/>
	Positive Stop	<input checked="" type="checkbox"/>	ABA-2	OSHA w/ TWA*	<input type="checkbox"/>	Vermiculite		
ABEPA	PLM EPA 400 Point Count	<input type="checkbox"/>	ABTEM	TEM AHERA	<input type="checkbox"/>	ABB	PLM EPA 600/R-93/116	<input type="checkbox"/>
ABB1K	PLM EPA 1000 Point Count	<input type="checkbox"/>	ABATN	TEM NIOSH 7402	<input type="checkbox"/>	ABEPA3	PLM EPA 400 Point Count	<input type="checkbox"/>
ABBEN	PLM EPA NOB**	<input type="checkbox"/>	ABT2	TEM Level II	<input type="checkbox"/>	ABCM	Cincinnati Method	<input type="checkbox"/>
ABBCH	TEM Chatfield**	<input type="checkbox"/>	Other:		<input type="checkbox"/>	Dust		
ABBTM	TEM EPA NOB**	<input type="checkbox"/>	New York ELAP			ABWA	TEM Wipe ASTM D-6480	<input type="checkbox"/>
ABQ	PLM Qualitative	<input type="checkbox"/>	ABEPA2	NY ELAP 198.1	<input type="checkbox"/>	ABDMV	TEM Microvac ASTM D-5755	<input type="checkbox"/>
** Available on 24-hr. to 5-day TAT			ABENY	NY ELAP 198.6 PLM NOB	<input type="checkbox"/>	Matrix Other		
Water			ABBNY	NY ELAP 198.4 TEM NOB	<input type="checkbox"/>			
ABHE	EPA 100.2	<input type="checkbox"/>		Positive Stop	<input type="checkbox"/>			

Turn Around Times	3 HR (4 HR TEM) <input type="checkbox"/>	6 HR (8HR TEM) <input type="checkbox"/>	12 HR <input type="checkbox"/>	1 Day <input checked="" type="checkbox"/>
	<input type="checkbox"/> 2 Days	<input type="checkbox"/> 3 Days	<input type="checkbox"/> 4 Days	<input type="checkbox"/> 5 Days

Special Instructions	
----------------------	--

Sample #	Sample Identification/Location	Volume or Area	Sample Date	Flow Rate*	Start – Stop Time*
01	3 Layer SVF & Mastic / Laundry, Kitchen, Dining				
02	3 Layer SVF & Mastic / Laundry, Kitchen, Dining				
03	Sheet Vinyl Floor / Bathroom				
04	Sheet Vinyl Floor / Bathroom				
05	Cove / Kitchen				
06	Cove & Mastic / Laundry				
07	Sink / Kitchen				
08	Sink / Kitchen				
09	GWB, Joint Compound, Texture / Bedrm 1 walls				
10	GWB, Joint Compound, Texture / Bedrm 2 walls				
11	GWB, Joint Compound, Texture / Livign Rm walls				
12	GWB, Joint Compound, Texture / Kitchen walls				

Relinquished by	Date	Time	Received by	Date	Time
EW	3/11/24	8:50am	<i>[Signature]</i>	3/14/24	10:35 AM

If no technician is provided, then the primary contact for your account will be selected. Unless scheduled, the turnaround time for all samples received after 3 pm EST will be logged in the next business day. Weekend or holiday work must be scheduled ahead of time and is charged at 150% of the 3hr TAT or a minimum charge of \$150. A courier charge will be applied for same day and one-day turnaround times for offsite work. SanAir covers Ground and Next Day Air shipping. Shipments billed to SanAir with a faster shipping rate will result in additional charges.

Form 140, Revision 1, 1/20/2017

If no technician is provided, then the primary contact for your account will be selected. Unless scheduled, the turnaround time for all samples received after 3 pm EST will be logged in the next business day. Weekend or holiday work must be scheduled ahead of time and is charged at 150% of the 3hr TAT or a minimum charge of \$150. A courier charge will be applied for same day and one-day turnaround times for offsite work. SanAir covers Ground and Next Day Air shipping. Shipments billed to SanAir with a faster shipping rate will result in additional charges. Page of 2 2